

# Sauna Delivery & Installation Checklist



## SECTION 1 — Site Preparation

- Ensure sauna location is level and stable (concrete, pavers, or reinforced decking recommended)
- Confirm adequate space and ventilation clearance
- Verify proper drainage (no standing water)
- Plan for weather protection if outdoors

## SECTION 2 — Access & Delivery

- Confirm clear access path (measure gates, doors, hallways, stairs)
- Ensure components can be safely transported to final location
- Remove all obstacles prior to delivery

## SECTION 3 — Assembly Preparation

- Have tools + experience, OR a qualified individual scheduled
- Plan for minimum 2 people
- Allow 4–5 hours for assembly
- Review instructions before starting

## SECTION 4 — Electrical Requirements (CRITICAL)

- Schedule a licensed electrician in advance
- Confirm voltage & amperage requirements
- Ensure dedicated circuit + proper wiring installed

### IMPORTANT DISCLAIMER:

Nordic Teak is not responsible for issues caused by improper electrical installation. Any heater-related issues must be diagnosed directly through the heater manufacturer.

## SECTION 5 — Delivery Day

- Inspect all components immediately upon arrival
- Report damage/missing items within 24 hours
- Keep packaging until installation is complete

Questions before installation? Contact Nordic Teak Support  
Proper preparation ensures longevity, safety, and optimal performance